CR 456 (Gulf Blvd) Lewis Pass Bridge Project

Project Development & Environment (PD&E) Study

FM No. 415253-1

Construction Options

Evaluation Factors	Detour/Temporary Bridge	
Description	While the existing bridge is replaced, detour traffic approximately 200’ to the west of the existing bridge on to a temporary bridge.	While the existing bridge is replaced, detour traffic to the west side of the existing bridge on to a temporary bridge.
	Option 1	Option 2
Construction Duration (Approximate # of Months)	18 Months	18 Months
Wetland Impacts (Acres)	(Permanent 0.01 Ac) (Temporary 0.01 Ac)	(Permanent 0.01 Ac) (Temporary 0.01 Ac)
Cedar Trees (Approximate # of Trees)	2	1
Construction Costs	$1,140,000	$1,133,000
Right-of-way Costs	$400,000	$1,220,000
Utility Costs	Minimal	Minimal
Estimated Total Project Costs	$1,540,000	$2,353,000